

Interface localization in the 2D Ising model with a driven line

O Cohen and D Mukamel

Department of Physics of Complex Systems, Weizmann Institute of Science, Rehovot 76100, Israel

E-mail: or.cohen@weizmann.ac.il and david.mukamel@weizmann.ac.il

Abstract. We study the effect of a one-dimensional driving field on the interface between two coexisting phases in a two dimensional model. This is done by considering an Ising model on a cylinder with Glauber dynamics in all sites and additional biased Kawasaki dynamics in the central ring. Based on the exact solution of the two-dimensional Ising model, we are able to compute the phase diagram of the driven model within a special limit of fast drive and slow spin flips in the central ring. The model is found to exhibit two phases where the interface is pinned to the central ring: one in which it fluctuates symmetrically around the central ring and another where it fluctuates asymmetrically. In addition, we find a phase where the interface is centered in the bulk of the system, either below or above the central ring of the cylinder. In the latter case, the symmetry breaking is ‘stronger’ than that found in equilibrium when considering a repulsive potential on the central ring. This equilibrium model is analyzed here by using a restricted solid-on-solid model.

PACS numbers: 05.50.+q, 05.70.Ln and 64.60.Cn

1. Introduction

The properties of an interface separating two coexisting phases in two-dimensions has been studied extensively in the past. Many of these studies deal with the wetting transition between a ‘dry’ phase where the interface is attached to the boundary and a ‘wet’ phase where it is found in the bulk. This transition has been observed in various experimental settings (see review in [1]), as well as studied theoretically (see review in [2] and various studies in [3–25]). In most theoretical models considered, when the system is its wet phase, the interface performs a random walk in the bulk of the system in a potential that becomes flat in the thermodynamic limit. An interesting question, with significant experimental implications, is whether and how the interface can be confined to a certain region of the system or pinned to a specific line.

One of the prominent prototypical models studied in this context is the two-dimensional Ising model with Glauber (spin-flip) dynamics. The phase diagram of the equilibrium Ising model with cylindrical boundary conditions has been analyzed in the past using its exact solution [3, 26]. In the ordered phase and for boundary magnetic fields that are of opposite signs, the model exhibits an interface between a positive and a negative magnetic phases. When the weaker of the two boundary fields is of small enough amplitude, the model is in a ‘dry’ phase where the interface is attached to this boundary. As this boundary field increases, the model undergoes a second order wetting transition where the interface detaches from the boundary and moves to the bulk of the system. This transition has been studied analytically in more general geometries in [21, 27].

One natural way to confine the interface in the bulk is to modify the interaction strength of the model in a single line. This approach has been considered in [28, 29], by studying an Ising model on a cylinder where the interaction strength within the central ring of the cylinder, denoted by J_0 , is smaller than that in the bulk, denoted by J . As often done in the study of wetting phenomena, the full two-dimensional model has been approximated in these studies by a one-dimensional restricted solid on solid (RSOS) model, which is more analytically tractable. The RSOS model describes the position of a sharp interface between pure positive and negative magnetic phases. The term ‘pure’ refers here to the absence of droplets of opposite sign in each phase. This description thus captures the low temperature behaviour of the full two dimensional Ising model. For $J_0 < J$ and with boundary fields that are strong enough to induce a wet phase, it was found that the interface is pinned to the central ring and fluctuates symmetrically around it. Here we complement this analysis by considering also the case where $J_0 > J$. In this case we find a phase where the interface is repelled from the central ring and confined to one of its sides. Note that here and below we use the terms ‘dry’ and ‘wet’ to describe the effect of the boundary layers, as opposed to ‘pinned’ and ‘repelled’, which describe the effect of the central ring.

The aim of this paper is to study a different mechanism for confining an interface, obtained by exerting a local driving field, which results in a non-equilibrium steady-

state. We study this mechanism by considering the example of the Ising model on a cylinder with Glauber dynamics (spin-flip) in the bulk and additional biased Kawasaki dynamics (spin-exchange) in the central ring of the cylinder.

In general, the addition of the biased Kawasaki dynamics to the equilibrium model results in a non-equilibrium steady-state measure which is unknown. However, as shown below, in the specific limit of fast drive and slow spin flips in the central ring of the cylinder, the phase diagram of the model can be studied analytically. Based on the approach presented in [30] and employed for the magnetization-conserving version of our model in [31], the dynamics of the magnetization in the central ring, m_0 , can be shown to correspond in this limit to an equilibrium random walk in a potential. This simplification is due to the fact that between every spin flip in the central ring, the bulk of the system above and below this ring relaxes to the steady-state of the two-dimensional Ising model. The effective potential, within which m_0 evolves, can be derived from the exact solution of the 2D Ising model, presented in [26]. For the purpose of our analysis this solution, originally presented for the case of a single boundary field, is generalized below to the case of two boundary fields.

The steady-state distribution of the random walker yields the large deviation function of m_0 , from which the phase diagram of the model can be derived. In addition to the pinned phase and repelled phase observed in the equilibrium RSOS model, we find an *asymmetrically-pinned phase* where the sign-flip symmetry of m_0 is spontaneously broken. The interface is pinned in this case to the central ring but fluctuates asymmetrically around it.

One important difference between the equilibrium and non-equilibrium cases involves the nature of the repelled phase. In both cases, the repelled phase is composed of two equally probable states where the interface is either below or above the central ring. In equilibrium, the system switches between these two states on a time-scale which grows polynomially with the height and circumference of the cylinder. By contrast, in the driven case, this time scale is found to grow exponentially with the circumference of the cylinder. We thus refer to the latter phase as a ‘strongly repelled phase’. This strong repulsion is assumed to be due to long-range correlations caused by the driving field, which are known to exist generically in driven systems [32–42].

The asymmetrically-pinned phase has also been observed by Sadhu et al. who studied the same model considered here, only with *conserving* Kawasaki dynamics in the bulk [31]. The original motivation for this work are experimental results on colloidal gas-liquid interface subjected to a shear flow parallel to the interface [43]. These experiments have shown that the shear drive applied away from the interface strongly suppresses the fluctuations of the interface, making it smoother. As found below, the driving field, considered in [31], causes a spontaneous breaking of the sign-flip symmetry of m_0 , yielding a phase where the interface exhibits stronger fluctuations in one of the sides of the central ring. The analytic analysis of this *conserving* model was possible for strong drive, slow spin flips on the central ring and low temperature. In the present study, we analyze the *non-conserving* model in a similar limit but for finite

temperatures. We are thus able to gain a better understanding of the fluctuations of the interface observed numerically in [31].

We complement the theoretical study by numerical simulation of the Ising model with a driven line. Interestingly, the two pinned phases and the strongly-repelled phase, found analytically for fast drive and slow spin-flips on the central ring, are found to exist significantly away from this limit.

The paper is organized as follows: In section 2 we define the Ising model with a driven line. In section 3.1 we discuss some of the properties of the equilibrium Ising model with $J_0 = J$, obtained from the exact solution of the 2D Ising model [26]. These properties are used in the derivation of the non-equilibrium model and provide a context for our present work. The properties of the equilibrium model for $J_0 \neq J$ are analyzed using a solid-on-solid model in section 3.2. The analysis of the non-equilibrium Ising model with a driven line is carried out in section 4.1. Section 4.2 presents results of Monte Carlo simulations which support some of the results of section 4.1. Concluding remarks are provided in section 5.

2. The Ising model on a cylinder with a driven line

The Ising-type model studied below is defined on a cylinder of size $L \times (2M + 1)$, illustrated in figure 1. A micro-configuration of the model is denoted by $\sigma \equiv \{\sigma_{i,j}\}$, where $i \in [1, L]$, $j \in [-M, M]$ and $\sigma_{i,j} = \pm 1$. Every spin in the system evolves by Glauber dynamics defined for spin i, j as

$$\sigma \xrightarrow{p_{i,j}^{(\text{Gb})} e^{-\frac{1}{2}\beta\{H[\sigma^{(i,j)}] - H[\sigma]\}}} \sigma^{(i,j)}, \quad (1)$$

where $\sigma^{(i,j)}$ is the original spin-configuration obtained after flipping the spin (i, j) in σ . Here $p_{i,j}^{(\text{Gb})}$ denotes the local rate of the Glauber dynamics. These rates affect the steady-state of the model only when a driving field is present. In our analysis of the non-equilibrium steady-state of the model in section 4 we consider the limit where the dynamics on the central ring is slower, i.e. $p_{i,0}^{(\text{Gb})} \ll p_{i,j \neq 0}^{(\text{Gb})} = 1$. The Hamiltonian in (1) is defined as

$$\begin{aligned} H[\sigma] = & -J \sum_{i=1}^L \sum_{j=-M}^{j=M-1} (\sigma_{i,j} \sigma_{i,j+1} + \sigma_{i,j} \sigma_{i+1,j}) \\ & - (J_0 - J) \sum_{i=1}^L \sigma_{i,0} \sigma_{i+1,0} - \sum_{i=1}^L (h_{\downarrow} \sigma_{i,-M} + h_{\uparrow} \sigma_{i,M}), \end{aligned} \quad (2)$$

where J denotes the coupling strength in the bulk, J_0 is the coupling strength within the central ring and $h_{\downarrow}, h_{\uparrow}$ are the boundary fields at the bottom and top of the cylinder, respectively (see figure 1). The periodic boundary condition is taken into account in (2) by considering $\sigma_{L+1,j} = \sigma_{1,j}$.




Figure 1. Cylindrical lattice with the drive on the central ring and the boundary fields indicated.

In addition to the Glauber dynamics in (1), the model is driven out of equilibrium by Kawasaki dynamics on the central ring defined by the following rates:

$$+ - \xrightleftharpoons[p^{(\text{Kw})}(1-q)]{p^{(\text{Kw})}q} - +, \quad (3)$$

where q controls the asymmetry of the dynamics and $p^{(\text{Kw})}$ is the rate of the Kawasaki dynamics. It is important to note that even for $q = 1/2$ the model is out of equilibrium. The equilibrium Ising model is retained only when considering $p^{(\text{Kw})} = 0$.

In section 3 we discuss the properties of the equilibrium model ($p^{(\text{Kw})} = 0$). In the case where $J_0 = J$ the model reduces to the standard 2D Ising model which has been studied analytically by many authors. When the boundary fields are of opposite sign the model exhibits an interface between a plus phase and a minus phase. The model undergoes a second order wetting transition when T is fixed and the boundary fields are increased (or conversely when the boundary fields are fixed and T is decreased). For $J_0 \neq J$, we study the model by considering the corresponding restricted solid on solid (RSOS) model, which is found to exhibit a phase where the interface is pinned to the central ring for $J_0 < J$ and a phase where it is ‘weakly repelled’ from the central ring for $J_0 > J$. The terms weakly is clarified below. The non-equilibrium case is analyzed analytically in section 3.1 in the limit of fast driven and slow spin flips in the central ring, $p_{i,0}^{(\text{Gb})} \ll p_{i,j \neq 0}^{(\text{Gb})} \ll p^{(\text{Kw})}$. The qualitative picture, which emerges from the analytic analysis, is confirmed numerically in section 4.2.

3. Analysis of the equilibrium Ising model

3.1. Wetting transition in the equilibrium model with $J_0 = J$

In this section we review the phase diagram of the equilibrium Ising model ($J_0 = J$ and $p^{(\text{Kw})} = 0$), as obtained using the exact solution of the model, presented in the treatise by McCoy and Wu [26]. The authors have studied the Ising model on a cylinder with

a single boundary field, e.g. for $h_\uparrow = 0$. In Appendix A we generalize their solution to the case of two boundary fields, where one finds a non-trivial phase diagram. This phase diagram can also be obtained based on the analysis of Abraham in [3]. We chose, however, to use the solution in [26] since it readily yields an expression for the boundary magnetization (of the top and bottom rings), necessary for the analysis in section 4.1.

The partition function of the equilibrium Ising model on a cylinder is given by

$$Z = \sum_{\sigma} e^{-\beta H[\sigma]}, \quad (4)$$

where $H[\sigma]$ is defined in (2) and J_0 is taken in this section to be $J_0 = J$. In [26] the logarithm of this function is computed explicitly for $h_\uparrow = 0$ and written as

$$-\frac{1}{\beta} \ln Z = 4L(2M+1)F + 2L\mathcal{F}_0 + L\mathcal{F}(h_\downarrow) + \mathcal{O}(1). \quad (5)$$

Here F is the well-known bulk-free-energy of the Ising model, $\mathcal{F}_0$ is the free energy of each boundary in the absence of a magnetic field and $\mathcal{F}(h_\downarrow)$ is the leading order contribution in L of the magnetic field to the free energy. These free energies are defined in terms of integrals over an angle θ , which result from the Fourier transform over the horizontal coordinate. More details are provided in section VI of [26] and in Appendix A. The bulk-free-energy is given by

$$F = -\frac{1}{\beta} \left\{ \ln[2 \cosh^2(\beta J)] + \frac{1}{4\pi} \int_{-\pi}^{\pi} d\theta \ln[z_J(1 - z_J^2)\alpha] \right\} \quad (6)$$

where $z_J \equiv \tanh(\beta J)$ and α is the solution with the larger magnitude of the following quadratic equation:

$$(1 + z_J^2)^2 - 2z_J(1 - z_J^2) \cos \theta - z_J(1 - z_J^2)(\alpha + \alpha^{-1}) = 0. \quad (7)$$

The boundary free energy in the absence of a boundary field is given in terms of α by

$$\mathcal{F}_0 = -\frac{1}{\beta} \left\{ -\ln[\cosh(\beta J)] - \frac{\ln 2}{2} + \frac{1}{4\pi} \int_{-\pi}^{\pi} d\theta \ln \left[1 + \frac{1 - z_J^4 - 2z_J(1 + z_J^2) \cos \theta}{z_J(1 - z_J^2)(\alpha - \alpha^{-1})} \right] \right\}. \quad (8)$$

The field-dependent boundary free energy, which is studied extensively below, is given by

$$\mathcal{F}(h) = -\frac{1}{\beta} \left\{ \ln[\cosh(\beta h)] + \frac{1}{4\pi} \int_{-\pi}^{\pi} d\theta \ln \left[1 - \frac{z_h |1 + e^{i\theta}|^2}{z_J(1 + z_J^2 + 2z_J \cos \theta) - (1 - z_J^2)\alpha} \right] \right\} \quad (9)$$

where $z_h \equiv \tanh(\beta h)$.

In Appendix A we show that the free energy for $h_\uparrow \neq 0$ and $h_\downarrow \neq 0$ is given by

$$-\frac{1}{\beta} \ln Z = 4L(2M+1)F + 2L\mathcal{F}_0 + L\mathcal{F}(h_\downarrow) + L\mathcal{F}(h_\uparrow) + \mathcal{O}(1). \quad (10)$$

The fact that the $\mathcal{O}(L)$ term is simply a sum over those in (5) over the two fields, $h_\downarrow$ and $h_\uparrow$, suggests that the two boundaries affect the system independently. However, there are coupling terms between the fields in the $\mathcal{O}(1)$ terms, which determine the overall magnetization of the system, i.e. the position of the interface.




Figure 2. The boundary magnetization in the two-dimensional model as a function of the magnetic field. The thick solid and dashed line denote $\mathcal{M}(h)$ and $\mathcal{M}_d(h)$, respectively.

In the analysis of the driven Ising model, defined in section 2, we use the expression for the boundary magnetization of the equilibrium model, obtained from the derivative of $\mathcal{F}(h)$ as

$$\mathcal{M}(h) = - \frac{d\mathcal{F}(h)}{dh} \quad (11)$$

$$= z_h + z_h \frac{z(1 - z_J^2)}{2\pi} \int_{-\pi}^{\pi} d\theta \frac{|1 + e^{i\theta}|^2}{z_h^2 z_J |1 + e^{i\theta}|^2 - z_J^2 (1 + z_J^2 + 2z_J \cos \theta) + z_J (1 - z_J^2) \alpha}$$

The properties of $\mathcal{M}(h)$ are analyzed in detail in Sec. VI.5 of [26] for the case of a single boundary field, obtained here by setting $h_{\uparrow} = 0$. In this case, below the Ising critical temperature, $T_c \approx 2.269J/k_B$, the boundary magnetization, $\mathcal{M}(h_{\downarrow})$, exhibits a discontinuity at $h_{\downarrow} = 0$ which signifies a sign flip of the bulk magnetization. This discontinuity is evident in figure 2, where $\mathcal{M}(h)$ is denoted by the thick solid line. McCoy and Wu have computed an additional solution for the boundary-magnetization using an analytic continuation of the integral in (11), which is given by

$$\mathcal{M}_d(h) = \mathcal{M}(h) + \frac{2z_h[(1 + z_J)^2(z_J^2 - z_h^2) - z_J^2(1 - z_J)^2(1 - z_h^2)]}{(r^{-1} - r)(1 - z_h^2)z_J(z_J^2 - z_h^2)^2}. \quad (12)$$

Here r denotes either of the two solutions of the following quadratic equation:

$$r + r^{-1} = \frac{2z_J^3 - 2z_h^4 z_J - z_J^2(1 - z_J^4)}{z_J(1 - z_h^2)(z_J^2 - z_h^2)}. \quad (13)$$

This analytic continuation of $\mathcal{M}(h)$, denoted by the two dashed lines in figure 2, is valid only in values of h where r is real, namely for $h \in [-h_w(T), h_w(T)]$, where

$$h_w(T) = \frac{1}{\beta} \operatorname{arctanh} \left[\sqrt{2 + z_J - 2 \frac{1 + z_J}{1 + z_J^2}} \right]. \quad (14)$$

The subscript d in $\mathcal{M}_d$ signifies that $\mathcal{M}_d$ is the magnetization when the system is in the dry phase and the interface is attached to the boundary. This interpretation is discussed below. Similarly $h_w(T)$ is the field where the wetting transition occurs.

In [26], where the case of $h_{\uparrow} = 0$ was studied, $\mathcal{M}_d(h_{\downarrow})$ is interpreted as a metastable solution which forms a hysteresis loop of the boundary magnetization. The hysteresis

loop is visible in figure 2 when combining the dashed and solid lines. When the system is on the dashed line the boundary field, $h_\downarrow$, and bulk magnetization are of opposite signs. In this case there exists a phase with a lower free energy, where the bulk magnetization switches sign and the interface moves to the other boundary where $h_\uparrow = 0$. The transition between those two states involves creating an interface in the bulk of the system. The free energy barrier between the metastable state and the ground state can thus be interpreted as the free energy difference between the case where the interface is attached to a boundary with a field $h_\downarrow$ and the case where it is in the bulk. This barrier vanishes for $|h_\downarrow| = |h_w(T)|$, where the dashed and solid lines in figure 2 meet.

In the case of where there are two non-vanishing boundary fields, (10) implies that the magnetization in the top and bottom lines should still be given by either $\mathcal{M}(h)$ or $\mathcal{M}_d(h)$ with $h = h_\uparrow, h_\downarrow$, respectively. However, the interpretation of each branch should be different in this case. When the two fields are of opposite signs, the state where the interface is attached to the field with the lower magnitude has the lower free energy out of the two dry states. We consider for concreteness the case where indeed $h_\uparrow h_\downarrow < 0$ and $|h_\downarrow| < |h_\uparrow|$. Using the above interpretation of the free energy barrier of the metastable state, it is clear that for $|h_\downarrow| < h_w(T)$ the state where the interface is attached to the lower boundary has a lower free energy than that of the wet state. In this case the magnetization of the lower boundary is given by $\mathcal{M}_d(h_\downarrow)$. On the other hand when $|h_\downarrow| > h_w(T)$ the state with the lowest free energy is that where the interface is found in the bulk. The boundary magnetization is given in this case by $\mathcal{M}(h_\downarrow)$. One can therefore write the magnetization of the lower boundary as

$$\mathcal{M}(h_\downarrow, h_\uparrow) = \begin{cases} \mathcal{M}_d(h_\downarrow) & |h_\downarrow| < \min(h_w(T), |h_\uparrow|) \quad \text{and} \quad h_\downarrow h_\uparrow < 0 \\ \mathcal{M}(h_\downarrow) & \text{else} \end{cases}, \quad (15)$$

Similarly, the expression for the upper-boundary magnetization can be obtained by exchanging $h_\uparrow$ and $h_\downarrow$ in the above equation.

Based on (15) we can draw the phase diagram of the Ising model on a cylinder with two boundary fields, shown for a fixed temperature below T_c in figure 3. The thin solid line denote a second order wetting transition, between a state where the interfaces is attached to one of the boundaries and a state where it is found in the bulk of the system. The thick solid line denotes a first order transition where the interface shifts from one boundary to the other. It is important to note that the bulk magnetization changes smoothly across the second order transition line. Close to the transition line the interface is not in the middle of the cylinder, but closer to one of the boundaries (although still $O(L)$ sites away from each). The exact position of the boundary can in principle be computed from the $\mathcal{O}(1)$ term in (10) which couples $h_\downarrow$ and $h_\uparrow$ explicitly.

One should note that the above interpretation of $\mathcal{M}_d(h)$ for the case of two boundary fields, from which (15) and the phase diagram given in figure 9 are derived, is done here on a heuristic level. A similar connection between $\mathcal{M}_d(h)$ and the wetting transition has already been mentioned in [21, 44]. A full mathematical proof of (15) based on the Pfaffian method employed by McCoy and Wu is beyond the scope of this




Figure 3. Phase diagram of the Ising model on a cylinder with two boundary fields, $h_\downarrow$ and $h_\uparrow$, for a fixed temperature below T_c . The thick and thin solid lines denote first and second order transition lines, respectively. The state of the system is sketched in boxes that signify a typical spin state in the cylinder, where light gray denotes the plus phase and dark gray denotes the minus phase.

paper.

It is also instructive to project the phase diagram of the model from the $h_\uparrow, h_\downarrow, T$ -space onto the $h_\uparrow = -h_\downarrow$ plane, as shown in figure 4. The diagram shows the ordered-disordered second order transition at the bulk critical temperature and a wetting transition at $h_\downarrow = h_\uparrow = h_w(T)$. The wetting temperature, T_w , has been derived in the past in [3]. This transition has been studied analytically also for different geometries in [21, 27].

3.2. RSOS analysis for $J_0 \neq J$

In general, the solution of the equilibrium model with $J_0 \neq J$ is unknown. However, as often done in the analysis of wetting phenomena, the qualitative behaviour of model can be analyzed by considering the corresponding restricted solid on solid (RSOS) model. Because RSOS models assume the two bulk phases to be pure (without droplets of phases of the opposite sign), they can be thought of as describing the low temperature behaviour of their corresponding two dimensional versions. In our case, the interface is described by an interface height variable, $h_i \in [-M, M+1]$, such that all the spin above (below) h_i are assumed to be of sign equal to that of $h_\uparrow$ ($h_\downarrow$). The Hamiltonian of the




Figure 4. Two dimensional projection of the phase diagram of the Ising model on a cylinder onto the $h_\uparrow = -h_\downarrow$ plane. The solid lines denote second order transitions between the three phases marked by the labels. The ordering of the bulk system occurs below the known Ising critical temperature, $T_c \approx 2.269J/k_B$. The wetting transition line occurs at $|h_\uparrow| = |h_\downarrow| = h_w(T)$ where $h_w(T)$ is given in (14).

RSOS model corresponding to the Hamiltonian in (1) is given by

$$H = LJ + J \sum_{i=1}^L \delta_{|h_{i+1}-h_i|-1} + (J_0 - J)[\delta_{h_i}\delta_{h_{i+1}-1} + \delta_{h_{i-1}}\delta_{h_{i+1}}], \quad (16)$$

and in addition $H = \infty$ whenever $|h_{i+1} - h_i| > 1$, which maintains the continuity of the interface. In this paper we are interested mainly in the dynamics of the central ring affects the wet phase. It is therefore sufficient to consider here the case where $h_\downarrow \rightarrow -\infty, h_\uparrow \rightarrow \infty$, in which the interface cannot be attached to the wall. The effect of the boundary fields can in principle be analyzed using the method described below.

Since the RSOS model is one-dimensional, its analysis can be done using the transfer matrix method. The transfer matrix corresponding to (16) is of dimension $(2M + 2) \times (2M + 2)$ and is given by

$$T_{i,j} = \begin{cases} e^{-\beta[J+J\delta_{|i-j|-1}+(J_0-J)(\delta_i\delta_{j-1}+\delta_{i-1}\delta_j)]} & |i-j| \leq 1 \\ 0 & \text{else} \end{cases}, \quad (17)$$

where $i, j \in [-M, M + 1]$. The partition function of the model can be computed using the eigenvalues of T , denoted by λ_m , as

$$Z = \text{tr}[T^L] = \sum_{m=1}^{2M+2} \lambda_m^L. \quad (18)$$

In addition, we denote by $|\psi^{(m)}\rangle$ the eigenvector corresponding to λ_m and by $\psi_i^{(m)}$ its $2M + 2$ components.

The properties of the different phases of the model can be understood by analyzing the probability distribution function (PDF) of h_i , which is of course independent of i .

In order to compute $Pr(h_i = j)$, it is useful to define a basis of vectors, $|\phi^{(j)}\rangle$ with $j = -M, \dots, M+1$, for which the j 'th entry is 1 and the rest are zero, i.e.

$$\phi_\ell^{(j)} \equiv \begin{cases} 1 & \ell = j \\ 0 & \text{else} \end{cases}. \quad (19)$$

In terms of $|\phi^{(j)}\rangle$ the PDF of h is given to using the density matrix approach as

$$Pr(h_i = j) = \frac{1}{Z} \langle \phi^{(j)} | T^L | \phi^{(j)} \rangle = \frac{1}{\sum_m \lambda^L} \langle \phi^{(j)} | \psi^{(m)} \rangle \lambda_m^L \langle \psi^{(m)} | \phi^{(j)} \rangle = \frac{\sum_m \lambda_m^L (\psi_j^{(m)})^2}{\sum_m \lambda^L}. \quad (20)$$

The PDF of h is thus fully described by the eigenvectors and eigenvalues of T . Analyzing the equation $T|\psi\rangle = \lambda|\psi\rangle$ for ψ_j with $j \neq 0, 1$, one find an equation of the form

$$\psi_{j-1}^{(m)} - 2\psi_j^{(m)} + \psi_{j+1}^{(m)} = (\lambda_m e^{2\beta J} - e^{\beta J} - 2)\psi_j^{(m)}. \quad (21)$$

On the central lines the finite Laplacian operator in the LHS above is slightly modified, yielding

$$e^{-\beta(J_0-J)}\psi_0^{(m)} - 2\psi_1^{(m)} + \psi_2^{(m)} = (\lambda_m e^{2\beta J} - e^{\beta J} - 2)\psi_1, \quad (22)$$

$$\psi_{-1}^{(m)} - 2\psi_0^{(m)} + e^{-\beta(J_0-J)}\psi_1^{(m)} = (\lambda_m e^{2\beta J} - e^{\beta J} - 2)\psi_0. \quad (23)$$

Equations (21)-(23) can be solved for $J_0 < J$ using the following Ansatz:

$$\psi_i^{(m)} = \begin{cases} A_m \sinh[k_m(M+1-i)] & 1 \leq i \leq M+1 \\ A_m \sinh[k_m(M+i)] & -M \leq i \leq 0 \end{cases}, \quad (24)$$

where k_m is a real exponent and A_m is a normalization factor. Inserting this form into (21) yields an expression for the eigenvalue, $\lambda_m = e^{-\beta J} + 2e^{-2\beta J} \cosh k_m$. Inserting this result and the ansatz into either (22) or (23) yields for the largest eigenvalue

$$k_1 = \text{acosh}\left[\frac{1 + e^{2\beta(J-J_0)}}{2e^{\beta(J-J_0)}}\right] + O(e^{-M}), \quad (25)$$

and additional solutions that are smaller than k_1 by an amount that does not scale with M . This gap between λ_1 and the second largest λ implies that the properties of the system are thus fully controlled by the highest eigenvalue of T . The fact that k_1 does not scale with M implies that the density profile of h decays in the bulk of the system as

$$\frac{P(h_i = \alpha M)}{P(h_i = 0)} \approx \left(\frac{\psi_{\alpha M}^{(1)}}{\psi_0^{(1)}}\right)^2 \sim e^{-M k_1 \alpha}. \quad (26)$$

The interface is thus pinned to the central ring for $J_0 < J$, with an exponentially small probability to be found in the bulk of the system. The interface fluctuates symmetrically around the central ring because it is energetically preferable for the interface to cross it. We verify this numerically in the full two-dimensional model and for a specific temperature in figure 5a. This phase is different from the asymmetrically pinned phase observed in the driven case below and in [31], where the interface fluctuates more into one side of the central ring.




Figure 5. The overall magnetization in the system, $m_T(\sigma) \equiv \frac{1}{L(2M+1)} \sum_{i=1}^L \sum_{j=-M}^M \sigma_{i,j}$, as a function of a rescaled time variable $\tau = t/[L(2M+1)]$ for $L = M = 100$. The temperature in both figures is $k_B T = 1.25$, which is below the Ising critical temperature. Figures (a) and (b) show the case where $J_0 = 0.5J$ and $J_0 = 1.5J$, respectively. In (a) the interface is pinned symmetrically to the central ring, whereas in (b) the interface is weakly-repelled from the central ring.

When analyzing the RSOS model with $J_0 > J$, one has to consider a different solution for the eigenvectors of T of the form

$$\psi_i^{(m)} = \begin{cases} A_m \sin[k_m(M+1-i)] & 1 \leq i \leq M+1 \\ A_m \sin[k_m(M+i)] & -M \leq i \leq 0 \end{cases}, \quad (27)$$

where k_m is a real wave-number. Inserting the above ansatz into (21) yields $\lambda_m = e^{-\beta J} + 2e^{-2\beta J} \cos k_m$. Inserting the latter result and (27) into either (22) or (23) yields

$$\cos(k_m) + \cot(k_m M) \sin(k_m) = e^{-\beta(J_0-J)}. \quad (28)$$

In general one expects k_m to scale as $1/M$ in order to yield a smooth density profile. As a result, there is no finite gap between the largest eigenvalue and others, which implies that many of the wavevectors ($O(M/\sqrt{L})$ of them) contribute to the density profile. Expanding the above equation in small k_m yields $\cot(k_m M) k_m \approx e^{-\beta(J_0-J)} - 1$, which suggests that k_m has the form $k = \frac{\pi m}{M} + \frac{\eta}{M^2} + O(M^{-3})$ with $m \neq 0$. Inserting this expansion yields for $m \ll M$

$$k_m = \frac{\pi m}{M} - \frac{\pi m}{M^2(1 - e^{-\beta(J_0-J)})} + O(M^{-3}), \quad (29)$$

and thus $\eta = -\pi m/(1 - e^{-\beta(J_0-J)})$. Solution with $m \sim M$ may have a different form, but they do not contribute to the density profile due to the λ_m^L factor in (20). Using this result the probability of the profile to touch the central ring can be shown to scale as

$$\frac{P(h_i = 0)}{P(h_i = \alpha M)} \sim \frac{\sum_m \lambda_m^L \sin^2(k_m M)}{\sum_m \lambda_m^L \sin^2[k_m(1-\alpha)M]} \approx \frac{\sum_m \lambda_m^L \sin^2(\eta/M)}{\sum_m \lambda_m^L \sin^2[(1-\alpha)\pi]} \sim \frac{1}{M^2}, \quad (30)$$

for any finite α . The interface is thus repelled from the central. This is clearly visible in figure 6 where $P(h_i = j)$ is plotted for a specific temperature and several system-sizes.




Figure 6. Numerical summation of the solution of $P(h_i = j)$ in Eqs. (20),(27) and (28) for $k_B T = 1.25$, $J_0 = 1.5J$ and $L = M = 20, 100, 400$. The probability rescaled by multiplication by M .

In terms of temporal behaviour of the interface, (30) implies that as long as L and M scale similarly the interface is confined either above or below the central line and very rarely touches the central ring. This is shown to be the case for the full 2D Ising model in figure 5b, where m_T is plotted for $L = M = 100$. When the interface is close to the central ring, there is an energetic barrier which scales as $2(J_0 - J)$ for creating a single crossing point. Expanding this crossing point has no energetic cost. There is, however, an entropic barrier which is expected to yield a crossing time between the two sides that grows polynomially with L and M . The analysis of the average crossing time, Δt for several system-sizes is shown figure 7, which suggested that $\Delta t \sim L^4$.

To conclude, modifying the interaction strength within the central ring was found yield two different wet phases. For $J_0 < J$ the interface is strongly pinned to the central ring and fluctuates symmetrically around it, whereas for $J_0 > J$ it is repelled from it but crosses it on a time-scale that grows polynomially with L and M . In the next section we study the effect of the drive on the interface and find that it leads to a different set of phases.

4. Analysis of the Ising model with a driven line

4.1. Phase diagram for fast drive and slow spin flips on the central ring

We now return to the Ising model with a driven line, illustrated in figure 1. In general the additional Kawasaki dynamics in (3) leads to a non-equilibrium steady-state, whose form is unknown. However, as explained below, one can derive the phase diagram of the model in the limit of fast drive and slow spin flips in the central ring. The different phases found in this study can be observed numerically also away from this limit, as




Figure 7. Average crossing time of the interface between the two sides of the central ring, plotted as a function of the length, L , on a log-log scale for $M = L$ and $k_B T = 1.25$. The dashed line denotes the curve $\Delta t \sim L^4$, which appears to fit the result.

shown in section 4.2.

The limit of fast drive is defined such that the relaxation time-scale of the conserving dynamics within the central ring is much faster than that of the boundary layers adjacent to that ring. Such a limit allows the conserving dynamics to reach a steady-state between every spin flip in the adjacent boundaries. The steady-state of the conserving dynamics is that of the Asymmetric Simple Exclusion Process (ASEP), which is uniform over all the spin-configurations with a fixed number of particles (which corresponds here to a fixed magnetization in the central ring) [39, 45, 46]. This steady-state is known to be obtained on a time-scale of $\mathcal{O}(L^{3/2})$ [47]. On the other hand, since the dynamics in the adjacent rings is non-conserving, their magnetization relaxes on a time-scale of $\mathcal{O}(1)/p_{i,j \neq 0}^{(\text{Gb})}$.

Similarly, the limit of slow spin flips in the central ring is defined such that the relaxation time-scale of the non-conserving dynamics in the central ring, given by $\mathcal{O}(1)/p_{i,0}^{(\text{Gb})}$, is much slower than the relaxation time of the adjacent layers. This enables the magnetization in these adjacent layers to reach the steady-state values of the 2D Ising model between every spin flip in the central ring. The limit we consider can thus be written as

$$p_{i,0}^{(\text{Gb})} \ll p_{i,j \neq 0}^{(\text{Gb})} \ll p^{(\text{Kw})} L^{-3/2}. \quad (31)$$

Within these two limits the rate of every spin flip in the central ring is a function only of magnetization in the central ring, defined as

$$m_0(\sigma) \equiv \frac{1}{L} \sum_{i=1}^L \sigma_{i,0}. \quad (32)$$

Summing over the rates of all the possible spin flips in the central ring, one obtains a

master equation for m_0 , which corresponds to that of one-dimensional random walk in a potential. This can be formally written as

$$\frac{dP(m_0)}{dt} = W_+(m_0 - \frac{2}{L})P(m_0 - \frac{2}{L}) + W_-(m_0 + \frac{2}{L})P(m_0 + \frac{2}{L}) - [W_+(m_0) + W_-(m_0)]P(m_0), \quad (33)$$

where $W_{\pm}$ are the rates of spin flips in the central ring for a given value of m_0 . These rates can be computed from the known steady-state properties of the 2D Ising model and of the ASEP, as discussed below. A similar approach has been employed in [31], where the rates were computed using a low temperature expansion of the Ising model. A finite temperature analysis was not possible in this case because the properties of the Ising model with a fixed magnetization (or equivalently fixed bulk magnetic field) are unknown. Equation (33) has a simple solution of the form

$$P(m_0) = \prod_{X=-L}^{Lm_0-2} \frac{W_+(X/L)}{W_-(X/L + 2/L)}, \quad (34)$$

where X increases in steps of 2. This can be written in the large L limit as

$$P(m_0) \propto e^{\frac{L}{2} \int_{-1}^{m_0} dx \{\log[W_+(x)/W_-(x)]\} + \mathcal{O}(1)} \equiv e^{L\mathcal{G}(m_0) + \mathcal{O}(1)}, \quad (35)$$

where $\mathcal{G}(m_0)$ is the large deviation function of m_0 .

Equation (35) implies that $\mathcal{G}(m_0)$ depends only on the ratio between $W_+(x)$ and $W_-(x)$. The first step in obtaining this ratio is to analyze the interaction between line 0 and its neighbouring lines from above and below. Naively one would think that for a given magnetization, m_0 , the spins in line 1 feel a magnetic field of strength Jm_0 . However, this turns out to be true only for high temperature, $\beta \rightarrow 0$. In order to verify this, one has to consider the ratio between the rate of a spin flip in site $(i, 1)$ and the that of the reverse process, given by

$$\frac{W_{\sigma_{i,1}=-1 \rightarrow \sigma_{i,1}=1}(m_0)}{W_{\sigma_{i,1}=1 \rightarrow \sigma_{i,1}=-1}(m_0 + 2/L)} = \frac{[P(\sigma_{i,0}=1|m_0)e^{\beta J} + P(\sigma_{i,0}=-1|m_0)e^{-\beta J}]e^{\beta J(\sigma_{i-1,1}+\sigma_{i+1,1}+\sigma_{i,2})}}{[P(\sigma_{i,0}=1|m_0)e^{-\beta J} + P(\sigma_{i,0}=-1|m_0)e^{\beta J}]e^{-\beta J(\sigma_{i-1,1}+\sigma_{i+1,1}+\sigma_{i,2})} + \mathcal{O}(1/L)}. \quad (36)$$

The fact that the steady-state measure of the central ring is uniform over all configuration implies that $P(\sigma_{i,0} = \pm 1|m_0) = (1 \pm m_0)/2$, which yields

$$\begin{aligned} \frac{W_{\sigma_{i,1}=-1 \rightarrow \sigma_{i,1}=1}(m_0)}{W_{\sigma_{i,1}=1 \rightarrow \sigma_{i,1}=-1}(m_0 + 2/L)} &= \frac{\frac{1+m_0}{2}e^{\beta J\sigma_{i,1}} + \frac{1-m_0}{2}e^{-\beta J}}{\frac{1+m_0}{2}e^{-\beta J} + \frac{1-m_0}{2}e^{\beta J}} e^{2\beta J(\sigma_{i-1,1}+\sigma_{i+1,1}+\sigma_{i,2})} + \mathcal{O}(\frac{1}{L}) \\ &\equiv e^{2\beta[\Phi_J(m_0) + J(\sigma_{i-1,1}+\sigma_{i+1,1}+\sigma_{i,2})]} + \mathcal{O}(\frac{1}{L}), \end{aligned} \quad (37)$$

where

$$\Phi_J(m) = -\frac{J}{2} \log \left[\frac{\cosh(\beta J) - m \sinh(\beta J)}{\cosh(\beta J) + m \sinh(\beta J)} \right]. \quad (38)$$

The spins in line 1 therefore feel an effective magnetic field $\Phi_J(m_0)$ which is in general different than Jm_0 . This field is plotted for various values of βJ in figure 8. Figure 8a demonstrates the fact that $\lim_{\beta \rightarrow 0} \Phi_J(m) = Jm$. The fact that $\Phi_J(m) \neq Jm$ was noted




Figure 8. Effective field induced between the driven line and the boundary line of the two-dimensional Ising model normalized by J , Φ_I/J , for different values of βJ .

also in [48], where the Ising interaction between two lines of spins was analyzed in the case where one line is strongly driven.

Since the spin flips in the driven line occur slowly, the systems above and below the driven line relax between every such spin flip to the steady-state of the 2D Ising model with boundary fields $h_\downarrow, \Phi_J(m_0)$ and $\Phi_J(m_0), h_\uparrow$, respectively $\ddagger$. Consequently, the magnetization in lines 1 and -1 is given on the time-scale in which m_0 is fixed by

$$m_1 = \mathcal{M}(\Phi_J(m_0), h_\uparrow), \quad m_{-1} = \mathcal{M}(\Phi_J(m_0), h_\downarrow). \quad (39)$$

Using an analysis similar to that of (37), the ratio between the rates of spin flips within the driven line are given by

$$\frac{W_{\sigma_{i,0}=-1 \rightarrow \sigma_{i,0}=1}(m_0)}{W_{\sigma_{i,0}=1 \rightarrow \sigma_{i,0}=-1}(m_0 + 2/L)} = e^{2\beta[2\Phi_{J_0}(m_0) + \Phi_J(m_1) + \Phi_J(m_{-1})]} + \mathcal{O}\left(\frac{1}{L}\right). \quad (40)$$

This implies that apart for the average magnetic field from the two adjacent rings, $\Phi_J(m_{-1})$ and $\Phi_J(m_1)$, every spin in the central ring feels a field of strength $2\Phi_{J_0}(m_0)$, exerted on it by the spins within the central ring.

The fact that the expression in (40) is independent of i , enables us to derive from it the ratio between the rates of increase and decrease of m_0 by summing over all possible single spin flips, yielding

$$\begin{aligned} \frac{W_+(m_0)}{W_-(m_0 + 2/L)} &= \frac{\sum_{i=1}^L \delta_{\sigma_{i,0},+1} W_{\sigma_{i,0}=-1 \rightarrow \sigma_{i,0}=1}(m_0)}{\sum_{i=1}^L \delta_{\sigma_{i,0},+1} W_{\sigma_{i,0}=1 \rightarrow \sigma_{i,0}=-1}(m_0 + 2/L)} \\ &= \frac{L(1+m_0)/2}{L(1-m_0)/2} e^{2\beta[2\Phi_{J_0}(m_0) + \Phi_J(m_1) + \Phi_J(m_{-1})]} + \mathcal{O}\left(\frac{1}{L}\right). \end{aligned} \quad (41)$$

Inserting the expression for $m_{\pm 1}$ in (39) into the above equation yields an expression for $W_+(m_0)/W_-(m_0)$ which is fully determined by m_0 and is given by

$$\frac{W_+(m_0)}{W_-(m_0)} = \frac{(1+m_0)}{(1-m_0)} e^{2\beta[2\Phi_{J_0}(m_0) + \Phi_J(\mathcal{M}(\Phi_J(m_0), h_\uparrow)) + \Phi_J(\mathcal{M}(\Phi_J(m_0), h_\downarrow))]} + \mathcal{O}\left(\frac{1}{L}\right). \quad (42)$$

$\ddagger$ The fact that the driven line exerts a field of strength $\Phi_J(m_0)$ and not Jm_0 was unaccounted for in [31]. However, by repeating the derivation presented there, we verified that the use of Φ_J does not change the qualitative results of that study.

Finally, the above result can be used in the solution of the large deviation function in (35), yielding

$$\mathcal{G}(m_0) = -\frac{1+m_0}{2} \log\left(\frac{1+m_0}{2}\right) - \frac{1-m_0}{2} \log\left(\frac{1-m_0}{2}\right) + 2\beta \int^{m_0} dx \Phi_{J_0}(x) \quad (43)$$

$$+ \beta \int^{m_0} dx \left[\Phi_J(\mathcal{M}(\Phi_J(m_0), h_\uparrow)) + \Phi_J(\mathcal{M}(\Phi_J(m_0), h_\downarrow)) \right].$$

Note that the first two terms in the RHS above correspond to the entropy of the central ring. The following two integrals account for the interaction within the central ring, and with the two adjacent rings, respectively.

By studying the extrema of $\mathcal{G}(m_0)$ for different values of β and J_0/J one can obtain the phase diagram of the model. The resulting phase diagram is plotted in figure 9 for the relatively simple case where $h_\downarrow < -J, h_\uparrow > J$, in which the interface is never attached to the boundaries of the cylinder. Representing plots of $\mathcal{G}(m_0)$ in each phase are provided in figure 10.

The main features of the phase diagram are as follows: In the driven model, the central line become magnetized before the bulk of the system does, i.e. for $T > T_c \approx 2.269J/k_B$. The system undergoes a second order phase transition between two phases where the bulk of the system is disordered and the central ring is either paramagnetic, $m_0 = 0$, or ferromagnetic, $m_0 \neq 0$. The plot of $\mathcal{G}(m_0)$ for this phase, referred here as the *ordered line* phase, is shown in figure 10a. Below the Ising critical point and for $J = J_0$ the system exhibits only one type of a wet phase, where the interface is repelled from the driven line, as shown in figure 10b. The sign-flip symmetry of m_0 is spontaneously broken in this phase, yielding two degenerate states, where the interface is either above or below the driven line. As suggested by the form $\mathcal{G}(m_0)$, there is a barrier between those two degenerate states which increases with L . This implies that the tunneling time between them increases exponentially with L , as confirmed numerically in the next section. This is in contrast to the polynomial growth of the crossing-time found in the equilibrium repelled phase in section 3.2. In this respect the repelled phase observed here can be considered to be a ‘strongly-repelled’ phase.

As in equilibrium, decreasing J_0 below J is generally expected to attract the interface to the driven line. However, in this case the effective repulsion due to the drive implies that one has to go significantly below $J_0 = J$ in order to observe a pinned phase. For $J_0 \lesssim 0.54J$, one finds two phases where the interface is pinned to the central ring. For relatively high temperatures, we observe a phase similar to that observed in equilibrium, where the interface fluctuates symmetrically around the central ring, yielding $m_0 = 0$ (corresponding LDF shown in figure 10c). The transition between this phase and the disordered phase is of first order (thick solid line in figure 9). As the temperature is decreased the sign-flip symmetry of m_0 is spontaneously broken, yielding a phase where the interface found in one of the sides of the central ring but at a distance from it that does not scale with L . The transition between the asymmetrically-pinned phase and the symmetrically-pinned phase is of second order. The plot of $\mathcal{G}(m_0)$ in the asymmetrically-pinned phase is shown in figure 10d. A reentrant second order transition




Figure 9. Phase diagram of the 2D Ising model with a driven line in the limit of strong drive and slow spin flips on the driven line. The boundary fields are such that prohibit a dry state, i.e. $h_\downarrow < -J$ and $h_\uparrow > J$. First and second order transition line are denoted by thick and thin solid lines, respectively. The dotted line denotes the stability limits of the two pinned phases. Here the boundary fields are given by $h_\downarrow < J$ and $h_\uparrow > J$, such that the system is always in the wet phase. Their exact values do not affect the results in this case.

back into the repelled phase is observed at lower temperature, where the field induced by the driven line is strong enough to unpin the interface, namely $|\Phi_J(m_0)| > |h_w(T)|$.

The asymmetrically-pinned phase was observed in [31], where Kawasaki dynamics was considered in the bulk and a low temperature limit was taken. The finite temperature fluctuation of the interface in this phase can thus be understood using the known boundary properties of the two-dimensional Ising model, analyzed extensively in [26].

4.2. Numerical results for the driven case

The phase diagram of the model presented in section 2 was computed in section 4.1 in the limit of $M \sim L \rightarrow \infty$, fast drive and slow spin flips on the central ring, $p_{i,0}^{(\text{Gb})} \ll p_{i,j \neq 0}^{(\text{Gb})} \ll p^{(\text{Kw})} L^{-3/2}$. In this section we test numerically whether the results obtained in that limit yield a correct qualitative picture for finite $L, p_{i,j}^{\text{Gb}}$ and p^{Kw} . For simplicity we consider here $M = L$. The results appear not to depend much on the ratio between $p_{i,0}^{\text{Gb}}$ and $p_{i,j \neq 0}^{\text{Gb}}$ and the asymmetry q or the drive. We thus choose to study here the simple case where $p_{i,j}^{\text{Gb}} = 1$ for all j 's and $q = 1$ (totally asymmetric Kawasaki dynamics). On the other hand we find very different results for large and small p^{Kw} . To test the prediction of the above analysis we considered relatively fast drive by taking $p^{\text{Kw}} = 1000$.




Figure 10. The effective potential for the random walk of m_0 , $V(m_0) = -\mathcal{G}(m_0)$, computed for the following points in the phase diagram in figure 9: (a) $\beta J = 0.35, J_0/J = 1$, (b) $\beta J = 0.5, J_0/J = 1$ (c) $\beta J = 0.66, J_0/J = 0.2$, (d) $\beta J = 2, J_0/J = 0.4$. The type of phase depicted in each figure is denoted in the corresponding caption. The dashed lines denote the value of m_0 for which $\Phi_J(m_0) = \pm h_w(T)$. For $|\Phi_J(m_0)| > |h_w(T)|$ the interface is detached from the boundary. Here the boundary fields are given by $h_\downarrow < J$ and $h_\uparrow > J$, such that the system is always in the wet phase. Their exact values do not affect the results in this case.

We focus here on the three different wet phases, which appear for $J_0 \lesssim 0.54J$. We consider specifically $J_0 = 0.4J$. The three phases are clearly visible when observing the time evolution of the overall magnetization, defined as

$$m_T(\sigma) \equiv \frac{1}{L(2M+1)} \sum_{i=1}^L \sum_{j=-M}^M \sigma_{i,j}. \quad (44)$$

Its behaviour in the repelled, symmetrically-pinned and asymmetrically-pinned phases is plotted respectively in Figs. 11a, 11b and 11c for $L = 50$ and in Figs. 11d, 11e and 11f for $L = 100$. In the repelled phase, the system can be in two degenerate state where the magnetization is significantly different from 0. The transitions between these two states are clearly visible for $L = 50$, but cannot be observed for $L = 100$ due to the limited simulation time. The exponential growth of the transition time is depicted by the grey triangles in figure 12, which shows the logarithm of the average time interval between the sign-flips of $m_T(\sigma)$ as function of L . The symmetrically-pinned phase, where $\langle m_T \rangle = 0$, appears in Figs. 11b and 11e to become more stable as the system-size increases. For system of size $L = 200$ we were unable to observe the detachment of the interface. In the asymmetrically-pinned phase, shown in Figs. 11c and 11f, the system moves between two states where $m_T \sim \pm \frac{1}{M}$. As shown by the squares in figure 12, the crossing-time of the interface between those states grows exponentially with L but at a




Figure 11. The overall magnetization, $m_t(\sigma)$, measured in simulation as a function of $\tau = t/L^2$ for $p^{(Kw)} = 1000$, $J_0 = J$, $M = L$ and $L = 50, 100$. The values of L and β used is mentioned in the caption of each figure. The three columns represent the three different ordered phases observed in the theoretical calculation in figure 9.




Figure 12. The logarithm of the transition time between the two degenerate ground state, $\ln(\Delta t)$, as a function of the system width, L , as measured for $L = M$, $p_{i,j}^{(Gb)} = 1$ and $p^{(Kw)} = 1000$. The hollow triangles ($\triangle$) represent the repelled phase, observed for $k_B T = 1.43$, whereas the squares ($\blacksquare$) represents the asymmetrically-pinned phase, observed at $k_B T = 0.5$. The dashed lines show the corresponding linear fits, with a slope of 0.072 in the pinned phase and a slope of 0.127 in the repelled phase.

smaller rate than that of the repelled phase.

The transitions between the various phases are examined in figure 13, which shows




Figure 13. Histogram of the total magnetization, $|m_T|$, and the magnetization on the central ring, $|m_0|$, as a function of the temperature. The data was measured for $L = M = 30$, $p_{i,j}^{(\text{Gb})} = 1$ and $p^{(\text{Kw})} = 1000$. Darker colours correspond for higher probability. The different phases as obtained in the limit of fast driven and slow spins flips on the central rings as denoted on the graph (OL for ordered line, R for repelled, SP for symmetrically-pinned AP for asymmetrically-pinned). The histogram of m_T is smoothen over to a scale of $1/M$.

the histogram of the absolute value of the overall magnetization, $|m_T(\sigma)|$, and of the magnetization on the driven line, $|m_0(\sigma)|$. The histogram is measured for a relatively small system size, $L = M = 30$, for which the transition between the different metastable states could be observed. Above the Ising critical temperature ($T_c \approx 2.269k_B T$) one finds a smooth transition into the ordered-line phase (OL) where $|m_0|$ increases 0 whereas $|m_T|$ is still relatively close to 0. Below it we find the repelled phase (R) where both $|m_0|$ and $|m_T|$ are large. At even lower temperatures there a coexistence of the repelled phase and the symmetrically-pinned (SP) phase, where $|m_0| \approx 0$ and $m_T \approx 0$. As the temperature is further decreased, the pinned phase turns into an asymmetrically-pinned (AP) where $|m_0| > 0$ and $m_T \sim \frac{1}{M}$. Finally at very low temperatures we find evidence for a reentrant transition into the repelled phase. For convenience, the state of the system at each phase is sketched in figure 14. These phases appear more or less at the temperatures calculated for fast drive and slow spin flips on the driven line. These theoretical transition points are denoted by the dashed lines in figure 13.




Figure 14. Sketch of the different phases shown in figure 13. The state of the system is sketched in boxes that signify a typical spin state in the cylinder, where light, dark gray and white denote the plus phase, minus phases and disordered phase, respectively.

5. Conclusions

We studied the Ising model on a cylinder with Glauber dynamics in the bulk and biased Kawasaki dynamics in the central ring of the cylinder. The purpose of this study is to analyze the effect of a localized drive on the properties of an interface between two coexisting phases.

In order to better understand the effect of the drive we considered a modified interaction strength within the central ring, J_0 , as well as analyzed the properties of the corresponding equilibrium model (where the drive is turned off). The equilibrium model has been studied previously for $J_0 < J$, using an approximate RSOS description. The model exhibits in this case a symmetrically-pinned phase, where the interface is pinned to the central ring and fluctuates symmetrically around it. We complemented this study by considering the case of $J_0 > J$, where the interface is found to be repelled from the central ring.

The driven model is analyzed in a special limit of fast drive and slow spin flips on the central ring. Within this limit, the large deviation of the magnetization on the central ring, m_0 , can be computed and the phase diagram of the model can be drawn. The driving field does not alter the critical temperature in this limit. Above the Ising critical temperature, the system exhibits a second order phase transition between a phase where the bulk is disordered and $m_0 = 0$, and a phase where the bulk is disordered but $m_0 \neq 0$. Below the critical temperature the system exhibits three different ordered phases: a repelled phase, where the interfaces is at a macroscopic distance from the central ring, a symmetrically-pinned phase, with $m_0 = 0$, and an asymmetrically-pinned phase, where the interface is at a microscopic distance from the central ring and thus $m_0 \neq 0$.

The repelled phase is found to be more stable in the driven model in the sense that the time it takes interface to cross the central ring increases exponentially with the circumference of the cylinder, L . This is in contrast with the equilibrium model with $J_0 > J$, where the crossing-time grows polynomially with L and the height of the cylinder, M . The strong repulsion of the interface in the driven case appears to be due to long-range correlation induced by the drive.

The asymmetrically-pinned phase, which was found only in the driven model, was observed also in the magnetization-conserving variant of our model in [31]. In this case the model can be studied analytically in the limit of strong drive, slow spin-exchanges with the central ring and low temperature. In the low temperature limit the authors have found only asymmetrically-pinned phase, in contrast to the repelled phase we find in the non-conserving model. In the present study we are able to go beyond the low temperature limit and draw the full phase diagram of the model. The finite temperature analysis gives a better insight into the fluctuations of the interface in the asymmetrically-pinned phase.

We test our observation numerically by simulating a finite system. When considering relatively fast drive, one finds the evidence for the different phases found analytically in the limit of fast drive and slow spin flips in the central ring.

Acknowledgments

We thank A. Bar, O. Hirschberg and T. Sadhu for helpful discussions. The support of the Israel Science Foundation (ISF) and of the Minerva Foundation with funding from the Federal German Ministry for Education and Research is gratefully acknowledged. We also thank the Galileo Galilei Institute for Theoretical Physics for the hospitality and the INFN for partial support during the completion of this work.

Appendix A. Solution of the Ising model on a cylinder with two boundary fields

In this appendix we present a generalization of the solution of the Ising model on a cylinder, derived in [26] for the case of a single boundary field, to the case two boundary fields. Since the two derivations are relatively similar, we refrain from repeating many of the details presented in [26] and simply emphasize the differences between the two cases.

The partition function of the Ising model is given

$$Z = \sum_{\sigma} e^{-\beta H[\sigma]}, \quad (\text{A.1})$$

where the Hamiltonian is defined for a system of size $L \times (2M + 1)$ as

$$H[\sigma] = -J \sum_{i=1}^L \sum_{j=-M}^{M-1} (\sigma_{i,j} \sigma_{i,j+1} + \sigma_{i,j} \sigma_{i+1,j}) + \sum_{i=1}^L (h_{\downarrow} \sigma_{i,-M} + h_{\uparrow} \sigma_{i,M}). \quad (\text{A.2})$$

The first step in the computation of Z is to write it in the following form:

$$\begin{aligned} Z = & \cosh^{4LM}(\beta J) \cosh^L(\beta h_{\uparrow}) \cosh^L(\beta h_{\downarrow}) \\ & \times \sum_{\sigma} \prod_{i=1}^L \prod_{j=-M}^{M-1} [(1 + z_J \sigma_{i,j} \sigma_{i,j+1})(1 + \sigma_{i,j} \sigma_{i+1,j})] \prod_{i=1}^L [(1 + z_{\downarrow} \sigma_{i,-M})(1 + z_{\uparrow} \sigma_{i,M})]. \end{aligned} \quad (\text{A.3})$$




Figure A1. Inset (a): the square lattice used in the partition sum in (A.7) is computed. The sum is over all the spanning graphs with weight of each graph is the product of edge weights, denoted in the graph. Inset (b): the mapping of each vertex in (a) into a four-vector, used in (A.8).

where

$$z_J = \tanh(\beta J), \quad z_{\downarrow} = \tanh(\beta h_{\downarrow}), \quad z_{\uparrow} = \tanh(\beta h_{\uparrow}). \quad (\text{A.4})$$

The sum in (A.3) can be expressed in a graphical form as

$$Z = 2^{L(2M+1)} \cosh^{4LM}(\beta J) \cosh^L(\beta h_{\uparrow}) \cosh^L(\beta h_{\downarrow}) \sum_{p,q,r} z_J^p z_{\downarrow}^q z_{\uparrow}^r N_{p,q,r}, \quad (\text{A.5})$$

where $N_{p,q,r}$ is the number of figures that can be drawn on the lattice in figure A1a with p inner bonds (denoted by z_J), q and r bonds connecting to the upper and lower lines respectively (denoted by $z_{\downarrow}$ and $z_{\uparrow}$, respectively) and with every bond used at most once.

Following the derivation in [26] the sum in (A.5) can be performed by counting all the spanning graphs in a corresponding directed graph obtained as follows: Every vertex in figure A1a is mapped into four vertices according to figure A1b, where a, b, c, d denote a general number which can be either $z_J, z_{\downarrow}$ or $z_{\uparrow}$. Single directed bonds in figure A1b can be drawn only in the stated direction and their weight is written above them. The weight of the double bonds in figure A1b is 1 when drawn in the direction of the arrow and -1 otherwise. The weights of the directed graph is the product of weights of all the bonds. This directed graph can be repressed by an adjacency matrix, A , whose dimension is $4L(2M+3) \times 4L(2M+3)$ and whose entries contain the weight of the bonds. For the sake of brevity we refrain from writing the form of the matrix explicitly. Its form for the case of a single boundary field can be found in Eq. VI.2.6 in [26].

As discussed in [26], the partition function can be written in terms of the Pfaffian of the adjacency matrix as

$$Z = 2^{L(2M+1)-1} \cosh^{4ML}(\beta J) \cosh^L(\beta h_{\uparrow}) \cosh^L(\beta h_{\downarrow}) \text{Pf} A. \quad (\text{A.6})$$

that obtained in [26] for case of a the single boundary field. Computing the determinant of tri-diagonal matrices of the form,

$$f_n = \begin{vmatrix} a_1 & b_1 & & & \\ c_1 & a_2 & b_2 & & \\ & c_2 & \ddots & \ddots & \\ & & \ddots & \ddots & b_{n-1} \\ & & & c_{n-1} & a_n \end{vmatrix}, \quad (\text{A.12})$$

can be done by the following recursive relation:

$$f_n = a_n f_{n-1} - c_{n-1} b_{n-1} f_{n-2}, \quad (\text{A.13})$$

where $f_0 = 1$ and $f_{-1} = 0$. Since in the bulk of the matrix $\varrho(\theta)$ repeats itself every two rows, i.e. $a_{n+2} = a_n, b_{n+2} = b_n, c_{n+2} = c_n$, it is useful to express the recursive relations of f_n and f_{n-1} as

$$\begin{pmatrix} f_n \\ f_{n-1} \end{pmatrix} = \begin{pmatrix} a_n a_{n-1} - c_{n-1} b_{n-1} & -a_n c_{n-2} b_{n-2} \\ a_{n-1} & -c_{n-2} b_{n-2} \end{pmatrix} \begin{pmatrix} f_{n-2} \\ f_{n-3} \end{pmatrix} \quad (\text{A.14})$$

For the analysis of $\det \varrho(\theta)$ we denoted by $\mathcal{R}_n$ and $\mathcal{D}_n$ the determinants of the submatrices of $\varrho(\theta)$ with the first $2n+2$ and $2n+1$ identical to those in (A.10), respectively.

Equations (A.10) and (A.14) imply that for $n > 1$

$$\begin{pmatrix} \mathcal{R}_n \\ z_J \mathcal{D}_n \end{pmatrix} = \begin{pmatrix} -a^2 + b^2 & a z_J \\ -a z_J & z_J^2 \end{pmatrix} \begin{pmatrix} \mathcal{D}_{n-1} \\ z_J \mathcal{D}_{n-1} \end{pmatrix}. \quad (\text{A.15})$$

For $n = 1$ one obtains a different equation, given by

$$\begin{pmatrix} \mathcal{R}_1 \\ z_J \mathcal{D}_1 \end{pmatrix} = \begin{pmatrix} -a^2 + b^2 & a z_J \\ -a z_J & z_J^2 \end{pmatrix} \begin{pmatrix} \mathcal{R}_0 \\ z_J^{-1} z_{\downarrow}^2 \mathcal{D}_0 \end{pmatrix} \quad (\text{A.16})$$

where $\mathcal{R}_0 = -c^2$ and $\mathcal{D}_0 = -c$. For reasons that will be clear below it is more useful to express the above equation as

$$\begin{pmatrix} \mathcal{R}_0 \\ z_J^{-1} z_{\downarrow}^2 \mathcal{D}_0 \end{pmatrix} = \begin{pmatrix} -c^2 \\ -z_J^{-1} z_{\downarrow}^2 c \end{pmatrix} = \begin{pmatrix} -c^2 & c z_J \\ -c z_J^{-1} z_{\downarrow}^2 & z_{\downarrow}^2 \end{pmatrix} \begin{pmatrix} 1 \\ 0 \end{pmatrix}. \quad (\text{A.17})$$

The recursion relation for the last two rows and columns of $\varrho(\theta)$ yields its determinant, given by

$$\begin{pmatrix} \det \varrho(\theta) \\ z_J \det \varrho'(\theta) \end{pmatrix} = \begin{pmatrix} -c^2 & -c z_J^{-1} z_{\uparrow}^2 \\ c z & z_{\uparrow}^2 \end{pmatrix} \begin{pmatrix} \mathcal{R}_{2M} \\ z \mathcal{D}_{2M} \end{pmatrix}, \quad (\text{A.18})$$

where $\varrho'(\theta)$ is the matrix in (A.14) with the last row and column removed. Equations (A.15)-(A.18) yield the following expression for $\det \varrho(\theta)$:

$$\begin{aligned} \det \varrho(\theta) &= \begin{pmatrix} 1 \\ 0 \end{pmatrix}^T \begin{pmatrix} -c^2 & -c z_J^{-1} z_{\uparrow}^2 \\ c z & z_{\uparrow}^2 \end{pmatrix} \begin{pmatrix} \mathcal{R}_{2M} \\ z \mathcal{D}_{2M} \end{pmatrix} \\ &= \begin{pmatrix} 1 \\ 0 \end{pmatrix}^T \begin{pmatrix} -c^2 & -c z_J^{-1} z_{\uparrow}^2 \\ c z_J & z_{\uparrow}^2 \end{pmatrix} \begin{pmatrix} -a^2 + b^2 & a z_J \\ -a z_J & z_J^2 \end{pmatrix}^{2M} \begin{pmatrix} -c^2 & c z_J \\ -c z_J^{-1} z_{\downarrow}^2 & z_{\downarrow}^2 \end{pmatrix} \begin{pmatrix} 1 \\ 0 \end{pmatrix}. \end{aligned} \quad (\text{A.19})$$

As in the standard transfer matrix method, the above equation can be expressed in terms of the eigenvalues and eigenvectors of the matrix in (A.15), denoted by λ_1, λ_2 and $\mathbf{v}_1$ and $\mathbf{v}_2$, yielding

$$\det \varrho(\theta) = \sum_{k=1,2} \left[\begin{pmatrix} 1 \\ 0 \end{pmatrix}^T \begin{pmatrix} -c^2 & -cz^{-1}z_{\uparrow}^2 \\ cz_J & z_{\uparrow}^2 \end{pmatrix} v_k \right] \lambda^{2M} \left[v_k^T \begin{pmatrix} -c^2 & cz_J \\ -cz_J^{-1}z_{\downarrow}^2 & z_{\downarrow}^2 \end{pmatrix} \begin{pmatrix} 1 \\ 0 \end{pmatrix} \right]. \quad (\text{A.20})$$

In [26], due to the absence of the upper magnetic field, $\det \varrho(\theta)$ is given by (A.20) with the first square brackets omitted. Inserting this back into Eqs. (A.7)-(A.8) is shown in [26] to yield

$$-\frac{1}{\beta} \ln Z = 4L(2M+1)F + L\mathcal{F}_0 + L\mathcal{F}(h_{\downarrow}) + \mathcal{O}(1), \quad (\text{A.21})$$

where F is given in (6),

$$\mathcal{F}(h) = -\frac{1}{\beta} \left\{ \ln[\cosh(\beta h)] + \frac{1}{4\pi} \int_{-\pi}^{\pi} d\theta \ln \left[1 - \frac{z_h |1 + e^{i\theta}|^2}{z_J(1 + z_J^2 + 2z_J \cos \theta) - (1 - z_J^2)\alpha} \right] \right\} \quad (\text{A.22})$$

and α is given in (7). Since the two square brackets in (A.20) have the same structure, it is clear that the first square bracket would yield the same free energy, yielding in the two-boundary-fields case the following free energy:

$$-\frac{1}{\beta} \ln Z = 4L(2M+1)F + 2L\mathcal{F}_0 + L\mathcal{F}(h_{\downarrow}) + L\mathcal{F}(h_{\uparrow}) + \mathcal{O}(1). \quad (\text{A.23})$$

References

- [1] DE Sullivan. Wetting transitions and multilayer adsorption at fluid interfaces. *Fluid interfacial phenomena*, page 45, 1986.
- [2] Kurt Binder, David Landau, and Marcus Müller. Monte carlo studies of wetting, interface localization and capillary condensation. *J. Stat. Phys.*, 110(3-6):1411–1514, 2003.
- [3] DB Abraham. Solvable model with a roughening transition for a planar ising ferromagnet. *Phys. Rev. Lett.*, 44:1165–1168, 1980.
- [4] Michael E Fisher and Hisao Nakanishi. Scaling theory for the criticality of fluids between plates. *J. Chem. Phys.*, 75(12):5857–5863, 1981.
- [5] Hisao Nakanishi and Michael E Fisher. Multicriticality of wetting, prewetting, and surface transitions. *Phys. Rev. Lett.*, 49:1565–1568, 1982.
- [6] Hisao Nakanishi and Michael E Fisher. Critical point shifts in films. *The Journal of chemical physics*, 78(6):3279–3293, 1983.
- [7] K Binder, DP Landau, and DM Kroll. Critical wetting with short-range forces: is mean-field theory valid? *Phys. Rev. Lett.*, 56(21):2272, 1986.
- [8] DB Abraham and ER Smith. An exactly solved model with a wetting transition. *J. Stat. Phys.*, 43(3-4):621–643, 1986.

- [9] K Binder and DP Landau. Wetting and layering in the nearest-neighbor simple-cubic ising lattice: A monte carlo investigation. *Phys. Rev. B*, 37(4):1745, 1988.
- [10] K Binder, DP Landau, and S Wansleben. Wetting transitions near the bulk critical point: Monte carlo simulations for the ising model. *Phys. Rev. B*, 40(10):6971, 1989.
- [11] EV Albano, K Binder, Dieter W Heermann, and W Paul. Adsorption on stepped surfaces: a monte carlo simulation. *Surface science*, 223(1):151–178, 1989.
- [12] EV Albano, K Binder, DW Heermann, and W Paul. Critical wetting in the square ising model with a boundary field. *J. Stat. Phys.*, 61(1-2):161–178, 1990.
- [13] AO Parry and R Evans. Influence of wetting on phase equilibria: A novel mechanism for critical-point shifts in films. *Phys. Rev. Lett.*, 64(4):439, 1990.
- [14] AO Parry and R Evans. Novel phase behaviour of a confined fluid or ising magnet. *Physica A*, 181(3):250–296, 1992.
- [15] K Binder, DP Landau, and AM Ferrenberg. Character of the phase transition in thin ising films with competing walls. *Phys. Rev. Lett.*, 74(2):298, 1995.
- [16] K Binder, DP Landau, and AM Ferrenberg. Thin ising films with competing walls: A monte carlo study. *Phys. Rev. E*, 51(4):2823, 1995.
- [17] K Binder, R Evans, DP Landau, and AM Ferrenberg. Interface localization transition in ising films with competing walls: Ginzburg criterion and crossover scaling. *Phys. Rev. E*, 53(5):5023, 1996.
- [18] A Maciol, J Stecki, et al. $d=2$ ising strip with two surface fields solved using the transfer-matrix method. *Phys. Rev. B*, 54(2):1128, 1996.
- [19] A Maciolek. Magnetization profiles for a ising strip with opposite surface fields. *J. Phys. A*, 29(14):3837, 1996.
- [20] Enrico Carlon and Andrzej Drzewiński. Critical point shift in a fluid confined between opposing walls. *Phys. Rev. E*, 57(3):2626, 1998.
- [21] C-E Pfister and Yvan Velenik. Interface, surface tension and reentrant pinning transition in the 2d ising model. *Communications in mathematical physics*, 204(2):269–312, 1999.
- [22] EV Albano, K Binder, and W Paul. Monte carlo studies of $d=2$ ising strips with long-range boundary fields. *Journal of Physics: Condensed Matter*, 12(12):2701, 2000.
- [23] A De Virgiliis, EV Albano, M Müller, and K Binder. Interfaces in the confined ising system with competing surface fields. *Physica A*, 352(2):477–497, 2005.
- [24] BJ Schulz, K Binder, and M Müller. First-order interface localization-delocalization transition in thin ising films using wang-landau sampling. *Phys. Rev. E*, 71(4):046705, 2005.
- [25] Lijun Pang, DP Landau, and K Binder. Simulation evidence for nonlocal interface models: Two correlation lengths describe complete wetting. *Phys. Rev. Lett.*, 106(23):236102, 2011.

- [26] Barry M McCoy and Tai Tsun Wu. *The Two-Dimensional Ising Model*. Harvard University Press, 1973.
- [27] DB Abraham and PJ Upton. Orientation dependence of surface critical phenomena in antiferromagnets: exact results in two dimensions. *Phys. Rev. Lett.*, 85(12):2541, 2000.
- [28] DB Abraham. Binding of a domain wall in the planar ising ferromagnet. *J. Phys. A*, 14(9):L369, 1981.
- [29] J M J Van Leeuwen and H J Hilhorst. Pinning of a rough interface by an external potential. *Physica A*, 107(2):319–329, 1981.
- [30] O. Cohen and D. Mukamel. Phase diagram and density large deviations of a nonconserving *abc* model. *Phys. Rev. Lett.*, 108:060602, 2012.
- [31] Tridib Sadhu, Zvi Shapira, and David Mukamel. Interface phase transition induced by a driven line in two dimensions. *Phys. Rev. Lett.*, 109(13):130601, 2012.
- [32] H Spohn. Long range correlations for stochastic lattice gases in a non-equilibrium steady state. *J. Phys. A*, 16:4275–4291, 1983.
- [33] P L Garrido, J L Lebowitz, C Maes, and H Spohn. Long-range correlations for conservative dynamics. *Phys. Rev. A*, 42(4):1954–1968, 1990.
- [34] J R Dorfman, T R Kirkpatrick, and J V Sengers. Generic long-range correlations in molecular fluids. *Annu. Rev. Phys. Chem.*, 45(1):213–239, 1994.
- [35] R K P Zia and B Schmittmann. Statistical mechanics of driven diffusive systems. In C Domb and J L Lebowitz, editors, *Phase Transitions and Critical Phenomena*, volume 17. Academic Press, London, 1995.
- [36] B Schmittmann and R K P Zia. Phase transitions and critical phenomena. In C Domb and J L Lebowitz, editors, *Statistical Mechanics of Driven Diffusive Systems*, volume 17. Academic Press, London, 1995.
- [37] S Lepri, R Livi, and A Politi. Thermal conduction in classical low-dimensional lattices. *Phys. Rep.*, 377(1):1–80, 2003.
- [38] J M Ortiz de Zárate and J V Sengers. On the physical origin of long-ranged fluctuations in fluids in thermal nonequilibrium states. *J. Stat. Phys.*, 115:1341–1359, 2004.
- [39] B Derrida. Non-equilibrium steady states: fluctuations and large deviations of the density and of the current. *J. Stat. Mech.*, 2007(07):P07023, 2007.
- [40] R A Blythe and M R Evans. Nonequilibrium steady states of matrix-product form: a solver’s guide. *J. Phys. A*, 40(46):R333, 2007.
- [41] A Dhar. Heat transport in low-dimensional systems. *Adv. Phys.*, 57(5):457–537, 2008.
- [42] Tridib Sadhu, Satya N Majumdar, and David Mukamel. Long-range steady-state density profiles induced by localized drive. *Phys. Rev. E*, 84(5):051136, 2011.

- [43] Didi Derks, Dirk GAL Aarts, Daniel Bonn, Henk NW Lekkerkerker, and Arnout Imhof. Suppression of thermally excited capillary waves by shear flow. *Phys. Rev. Lett.*, 97(3):038301, 2006.
- [44] Charles-Ed Pfister. Phase diagram of the half-infinite ising model. *J. Stat. Phys.*, 47(5):761–771, 1987.
- [45] Bernard Derrida, Eytan Domany, and David Mukamel. An exact solution of a one-dimensional asymmetric exclusion model with open boundaries. *J. Stat. Phys.*, 69(3-4):667–687, 1992.
- [46] Olivier Golinelli and Kirone Mallick. The asymmetric simple exclusion process: an integrable model for non-equilibrium statistical mechanics. *J. Phys. A*, 39(41):12679, 2006.
- [47] O Golinelli and K Mallick. Bethe ansatz calculation of the spectral gap of the asymmetric exclusion process. *J. Phys. A*, 37(10):3321, 2004.
- [48] HJ Hilhorst. Two interacting ising chains in relative motion. *J. Stat. Mech.*, 2011(04):P04009, 2011.